

TABLE No. 13  
SAFE WORKING LATERAL LOADS (PLF) 8" x 8" LINTELS

LINTEL		SAFE LATERAL LOADS (PLF)		LINTEL		SAFE LATERAL LOADS (PLF)	
Total Length	Type	8"x8" PLAIN	8"x8" SOLID	Total Length	Type	8"x8" PLAIN	8"x8" SOLID
2'-10"	Precast	1863	9813	10'-6"	Precast	154	692
3'-6"	Precast	1185	4641	11'-4"	Precast	122	629
4'-0"	Precast	931	3326	12'-0"	Precast	103	586
4'-6"	Precast	767	2592	12'-6"	Precast	91	558
4'-8"	Precast	724	2414	13'-4"	Precast	75	503
5'-4"	Precast	593	1895	14'-0"	Precast	65	454
5'-10"	Precast	504	1608	14'-8"	Prestressed	N.R.	417
6'-4"	Precast	450	1412	15'-4"	Prestressed	N.R.	369
6'-6"	Precast	435	1357	17'-4"	Prestressed	N.R.	257
6'-8"	Precast	420	1306	19'-4"	Prestressed	N.R.	184
7'-6"	Precast	348	1085	20'-0"	Prestressed	N.R.	167
7'-8"	Precast	338	1052	21'-4"	Prestressed	N.R.	139
8'-0"	Precast	321	991	22'-0"	Prestressed	N.R.	127
8'-4"	Precast	305	937	24'-0"	Prestressed	N.R.	100
9'-4"	Precast	222	806				


N.R.- NOT RECOMMENDED

**Samuel A. Greenberg**, State of Florida, Professional Engineer,  
License No. **34245**

This item has been digitally signed and sealed by  
**Samuel A. Greenberg**, PE the date shown using a Digital  
Signature (date is in the coded seal).

Printed copies of this document are not considered signed and sealed  
And the SHA authentication code must be verified on any  
electronic copies.



<b>DE</b> DANSCO ENGINEERING, P.A. 6423 RUBIA CIRCLE APOLLO BEACH - FLORIDA - 33512 PHONE - (813) 911 1524    8AM@DEPE@AOL.COM	8" x 8" PRECAST/PRESTRESSED LINTEL TABLE	
	Marion Masonry Materials of Ocala, LLC  3855 N.E. 35th Street Ocala, FL 34479 PH. (352) 629-9788	
© 2023 THESE DRAWINGS AND DESIGNS ARE THE JOINT PROPERTY OF DANSCO ENGINEERING, P.A. AND THE CLIENT ON THIS PROJECT. ANY REPRODUCTION OR UNAUTHORIZED USE IS PROHIBITED.	<input type="checkbox"/> SAMUEL A. GREENBERG, P.E. #34245	SHT. NO. <b>SK7</b> of 11